MARINE CIVIL ENGINEERING

Tokyo International Airport (Haneda Airport) (Tokyo, Japan)

Haneda Airport started in 1931 as a small nationally run airfield with a single 300-meter runway. Subsequent extensions were continuously carried out to keep pace with the continually increasing demand of the airport. To respond to this growth, Toa Corporation, too, moved forward with its state-of-theart civil engineering technologies. A new artificial island was completed at the Haneda Airport site and put to use for the 4th runway (2,500m). The construction was carried out in cooperation with multiple construction companies under a variety of difficult conditions, including using a hybrid pier/reclamation construction, a structure rarely used anywhere in the world, short construction periods, and quick execution under restrictions by airlines.

Operations

Toa Corporation's technologies were applied to nearly every part of the construction of the artificial island,

including improving the weak foundation soil and producing landfill material by hardening dredged soil. Furthermore, the company dedicated itself to ensuring quality by grasping the ever-changing

movements of the foundation in realtime through meticulous management of work execution that was reflected in subsequent processes.



Minami-Honmoku Container Terminal (Yokohama, Japan)

The Minami-Honmoku Pier is located at the Port of Yokohama, which is one of the ports in Keihin Port, a designated strategic international container port. With the aim of strengthening its international competitiveness, work is currently underway to make improvements to the facilities at the Minami-Honmoku Pier to transform it into an international container terminal capable of large-scale container ships to come alongside the quay. Columns measuring 32 meters high with a diameter of 24.5 meters constructed of steel sheet structure cellular were employed in the work to construct the earthquake-resistant quay's foundation. The quay will, in the future, have a façade that is sunk to a depth of 18 meters. Toa Corporation was involved in the project and successfully completed MC-3 phase and MC-4 phase(2007-2019).




Chubu Centrair International Airport (Aichi, Japan)

Chubu Centrair International Airport, inaugurated on February 7, 2005, is a first class airport with a 3,500m runway. It is designed to be the main international gateway to the Chubu (central) region of Japan. In order to be 24-hour operational, the airport is located in Ise Bay, 1.1km offshore of Tokoname City, Aichi Prefecture, to prevent disturbing local communities with airplane noise. Throughout the construction of the 470ha



Great East Japan Earthquake Disaster Recovery

The Great East Japan Earthquake that struck on March 11, 2011, caused devastating damage to the area inland from the coast, although the coastal disaster prevention forest along the coast of Miyagi Prefecture was effective to a certain degree, achieving such results as reducing damage from the subsequent tsunami. With the aim of realizing the early regeneration of the coastal disaster prevention forest through restoration of the damaged seawall and the land where subsidence had occurred, TOA took part in construction work on the embankment foundation and the restoration of the seawall.





artificial island, which commenced in November 2001, "Plug Magic" and "COS-NET," two of TOA's advanced technologies, played critical roles in building the 12km-long enclosing seawalls and reclaiming 56,000,000m³ of soil and earth in an economical, timely, safe, and environmentally-friendly manner. "Plug Magic" recycled the soft clayey material coming from dredging operations of navigational channels in Ise Bay into

construction material suitable for reclamation, and saved 8.630.000m³ of soil from having to be transported from onland sources in the vicinity. "COS-NET" was adopted by contractors involved in the projects as a common system to monitor and control working vessels, and ensure their smooth and safe navigation around the working area.



TOA's "Plug Magic" dredging method was adopted in order to maximize the recycling of dredged soft materials

projects related to not only the Great East Japan Earthquake, but also for earthquake damage, and wind and flood damage throughout the country.

Operations

MARINE CIVIL ENGINEERING

The Port Vila Lapetasi International Multi-Purpose Wharf Development Project (Vanuatu)

Construction work has been completed In order to handle the recent rapid on the Port Vila Lapetasi International Multi-Purpose Wharf Development Project on Efate Island, where the capital city of the South Pacific nation of the Republic of Vanuatu is located. This nation is made up of an archipelago of more than 80 islands stretching north to south. Many of the islands are experiencing a growing number of tourists who come to enjoy natural surroundings untouched by humans, which contributes to the nation's economic growth.

increase in the volume of cargo that has resulted from this growth, a development project to improve the facility to be an international multi-purpose wharf was carried out. In this project, a new quay, with a length of 200 meters and made to a depth of 12.3 meters below sea level to handle mainly container ships, was constructed at a location 500 meters east of the current harbor, which had been shared by both cargo ships and cruise ships.



Jebel Ali Container Terminal in Design and Construction (United Arab Emirates)

A new container terminal has been completed in Dubai of United Arab Emirates in March 2015. For this construction project, an existing general cargo berth was redesigned and renovated as a state-of-the-art container terminal.

Jebel Ali Port is the largest marine terminal in the Middle East and also has the largest man-made harbor in the world. With the completion of the new container terminal, Port Jebel Ali has become able to handle 19 million TEU containers a year.

This project involves renovating the

existing 1,860-meter berth at the Jebel Ali Free Zone Area (JAFZA), which is located in the United Arab Emirates and operated by DP World. Improvements was made to the existing berth (the quay has a depth of 11 meters) by constructing a container berth (1,860 meters) with a depth of 18 meters.

The work calls for the design and construction of container terminal including a 75-ha container vard behind the berth, building and Mechanical, Electrical and Plumbing (MEP) works.



Construction Work on Phase III of Container Terminal at Pasir Panjang Terminal (Singapore)

Singapore is one of the largest container handlers in the world. And the volume is increasing day by day. In order to alleviate congestion at the terminal in Singapore, and as part of an effort to increase the volume of containers to be handled, fifteen new berths were built at Pasir Panjang Container Terminal, without disrupting the operation of the terminal. Toa Corporation built 12 of the 15 berths

that were built, as well as a container yard having an area of approximately 160 ha. On the west side of this terminal, TOA has also built 14 berths and a container yard covering an area of 140 ha, all of which are currently in operation.



Newly Completed Project

Lomé Fishing Port Improvement Project

The Lomé Fishing Port Improvement Project was completed in the Republic of Togo.

This facility was constructed in a country with a population of approximately eight million people, making it possible for fresh fish and shellfish to be supplied to more than 800,000 people, most of whom live in the city of Lomé. In addition to the breakwater, idling guay, and other structures, facilities needed at a fishing port, such as a sorting area, wholesaling area, ice-making machine, and an administration office building equipped with toilets and other facilities, were constructed with the assistance of Grant Aid from the Japanese government. It is believed that this facility will become a base for supporting the diet of as many of the nation's people as possible.



Site of construction Lomé City, Republic of Togo

Namibe Port Rehabilitation Project

The Namibe Port Rehabilitation Project was completed in the Republic of Angola. This project was carried out with the assistance of Grant Aid from the Japanese government, and involved repair and maintenance work on the port facilities at Namibe Bay, which had suffered substantial deterioration. The work included restoration work on the guays, paving the yard, and installation of water supply facilities.

The construction work improved the efficiency and safety of various types of work being carried out in the port, such as increasing the volume of cargo handled, shortening the container handling cycle (loading and unloading work), and reducing the number of accidents when vessels are berthing, enabling this project to contribute to the development of the entire country.





■ Client Ministry of Agriculture, Livestock and Fisheries of the Republic of Togo Construction period March 2017 to July 2019

Project outline Outer port facilities (Breakwater, Seawall, Side closing dyke, End protection

Mooring facilities (Landing quay, Idling quay, Slipway, Control dyke) Maneuvering basin (Wave dissipating slipway. Port entrance wavebreaker.) On-land facilities (Fish handling facility, Wholesaler's area, Administration office. Public toilets. Electrical room. Elevated water tank. Guard room. Garbage collection depotentec)

Equipment (Ice-making machine, Equipment for fish handling/wholesaling, Equipment for inspection room)

Client Ministry of Transport of the Republic of Angola **Construction period** March 2018 to May 2019 Project outline Restoration work on guays Work to pave apron and container vard Work to improve roadbed for refrigerated containers Work to install water supply facilities Site of construction Namibe Province, the Republic of Angola